

City of Stamford  
 Main Street Over Mill River  
 Bridge No.02212  
 WMC Reference No.: **11060**

Federal Project No.:  
 State Project No.:  
 Date: August 4, 2014  
 Rev.:

**ALTERNATE 3 COST OPINION**

ConnDOT No.	ITEM	UNIT	RDWY QUANT.	BRIDGE QUANT.	UNIT PRICE	TOTAL COST
0201001	Clearing & Grubbing	LS	1		\$ 66,500.00	\$ 66,500.00
0202501	Cut Concrete Pavement	L.F.	270		\$ 5.43	\$ 1,466.10
0202502	Removal of Concrete Pavement	S.Y.	805		\$ 23.38	\$ 18,820.90
0202522 A	Removal of Bituminous Pavement	S.Y.	352		\$ 9.29	\$ 3,270.08
0203203	Structure Excavation - Earth (Excluding Cofferdam and Dewatering)	C.Y.		1665	\$ 27.00	\$ 44,955.00
0203302	Structure Excavation - Rock (Excluding Cofferdam and Dewatering)	C.Y.		85	\$ 228.00	\$ 19,380.00
0204001 A	Cofferdam and Dewatering	L.F.		390	\$ 246.20	\$ 96,018.00
0204151 A	Handling Water	L.S.		1	\$ 40,000.00	\$ 40,000.00
0205003	Trench Excavation (0-10' Deep)	C.Y.		80	\$ 22.00	\$ 1,760.00
0209001	Formation of Subgrade	S.Y.	395		\$ 5.38	\$ 2,125.10
0210306 A	Turbidity Control Curtains	L.S.	1		\$ 4,000.00	\$ 4,000.00
0210820	Water Polution Control	EST		1	\$ 5,000.00	\$ 5,000.00
0212002	Subbase	C.Y.	70		\$ 55.92	\$ 3,914.40
0216002	Pervious Structure Backfill	C.Y.		1625	\$ 42.80	\$ 69,550.00
0219001	Sedimentation Control System	L.F.	390		\$ 5.56	\$ 2,168.40
0406011	Bituminous Concrete - Class 1	Ton	215		\$ 150.00	\$ 32,250.00
0406017	Bituminous Concrete - Class 2	Ton	60		\$ 140.00	\$ 8,400.00
0502194 A	Maintaining Pedestrian Traffic (includes pedestrian bridge)	LS		1	\$ 200,000.00	\$ 200,000.00
0503001 A	Removal of Superstructure	LS		1	\$ 230,000.00	\$ 230,000.00
05030xx	Metalizing & Painting Existing Truss (includes containment and sand blasting)	LS		1	\$ 600,000.00	\$ 600,000.00
0507000	Remove Catch Basin	Ea.	2		\$ 500.00	\$ 1,000.00
0507002	Type "C" Catch Basin	Ea.	2		\$ 2,934.40	\$ 5,868.80
0507003 A	Type "C" Catch Basin w/Adjustable Curb Box	Ea.	1		\$ 1,500.00	\$ 1,500.00
0514205	Prestressed Deck Units(3'-0"x2'-3")	L.F.		1416	\$ 285.00	\$ 403,560.00
0521014	Steel- Laminated Elastomeric Bearings	Ea.		88	\$ 1,152.80	\$ 101,446.40
0601002	Class "A" Concrete	C.Y.		360	\$ 634.40	\$ 228,384.00
0601088 A	Concrete Form Liners	S.Y.		336	\$ 30.24	\$ 10,160.64
0601100	Class "C" Concrete	C.Y.		60	\$ 600.00	\$ 36,000.00
0601201	Class "F" Concrete	C.Y.		445	\$ 450.00	\$ 200,250.00
06016xx	Expansion Joint System	L.F.		80	\$ 96.00	\$ 7,680.00
0602001	Deformed Steel Bars	LB		47000	\$ 1.40	\$ 65,800.00
0602011 A	Deformed Steel Bars - Epoxy Coated	LB		11100	\$ 1.75	\$ 19,425.00
0603253 A	Disposal of Lead Debris	BBL.		1	\$ 500.00	\$ 500.00
0603271 A	Lead Health Protection Program(LHPP)	EST		1	\$ 22,500.00	\$ 22,500.00
0603858 A	Rehabilitation of Existing Trusses	LS		1	\$ 450,000.00	\$ 450,000.00
0651001	Bedding Material	C. Y	6		\$ 45.94	\$ 275.64
0651012	15" R.C. Pipe	L.F.	135		\$ 58.96	\$ 7,959.60
0703008	Intermediate Riprap	C. Y		130	\$ 72.40	\$ 9,412.00
0708001	Dampproofing	S. Y		230	\$ 14.66	\$ 3,371.80
0725002	Bagged Stone	C.F.		150	\$ 17.40	\$ 2,610.00
0728008 A	1/2" Crushed Stone	C.Y.		102	\$ 77.60	\$ 7,915.20
0755001	Geotextile	S.Y.		504	\$ 2.00	\$ 1,008.00
0811105	Cast in Place Concrete Curb	L.F.	365		\$ 60.00	\$ 21,900.00
0822001	Temporary Precast Concrete Barrier Curb	L.F.	300		\$ 40.58	\$ 12,174.00
0904937 A	Metal Bridge Rail - Three Rail (Combination)	L.F.		260	\$ 310.00	\$ 80,600.00

City of Stamford  
 Main Street Over Mill River  
 Bridge No.02212  
 WMC Reference No.: **11060**

Federal Project No.:  
 State Project No.:  
 Date: August 4, 2014  
 Rev.:

**ALTERNATE 3 COST OPINION**

ConnDOT No.	ITEM	UNIT	RDWY QUANT.	BRIDGE QUANT.	UNIT PRICE	TOTAL COST
0912013	Concrete Driveway Apron	S.F.	340		\$ 12.00	\$ 4,080.00
0913000	Remove Chainlink Fence	L.F.	65		\$ 6.73	\$ 437.45
0913011	5' Chain Link Fence w/ Top Rail	L.F.	310		\$ 49.48	\$ 15,338.80
0913068	6' Chain Link Fence w/Top Rail	L.F.	340		\$ 22.59	\$ 7,680.60
0913069	Temporary 6' Chain Link Fence	L.F.	306		\$ 13.00	\$ 3,978.00
0914001	A Metal Handrail	L.F.		60	\$ 205.73	\$ 12,343.80
0921001	Concrete Sidewalk	S.F.	3470		\$ 11.60	\$ 40,252.00
0944001	Furnishing and Placing Topsoil	S.Y.	380		\$ 10.93	\$ 4,153.40
0950005	Turf Establishment	S.Y.	380		\$ 4.21	\$ 1,599.80
0970004	Trafficman (City's Uniformed Police)	Est.	1		\$ 10,000.00	\$ 10,000.00
0971001	A Maintenance and Protection of Traffic	L.S.	1		\$ 100,000.00	\$ 100,000.00
0974001	A Removal of Existing Masonry	C. Y		590	\$ 201.00	\$ 118,590.00
0975002	Mobilization	L.S.	1		\$ 249,000.00	\$ 249,000.00
0976002	Barricade Warning Lights-High Intensity	Day	2700		\$ 1.00	\$ 2,700.00
0979003	Construction Barricade Type III	Ea.	15		\$ 132.80	\$ 1,992.00
0980001	Construction Staking	L.S.	1		\$ 33,500.00	\$ 33,500.00
1209005	Painted Pavement Markings-4" White	L.F.	400		\$ 1.00	\$ 400.00
1209007	Painted Pavement Markings-4" Yellow	L.F.	400		\$ 1.00	\$ 400.00
1209401	Painted Legend, Arrows & Markings	S.F.	15		\$ 1.40	\$ 21.00
1220011	Construction Signs-Type III Reflective Sheeting	S.F.	310		\$ 17.15	\$ 5,316.50
1403001	Manhole (Sanitary Sewer)	Ea.	1		\$ 3,994.20	\$ 3,994.20
SUBTOTAL						\$ 3,766,656.61
CONTINGENCY @ 25%						\$ 941,664.15
<b>2014 TOTAL</b>						<b>\$ 4,708,320.76</b>
<b>Projected 1 year to Year 2015 @ 4% per year</b>						<b>\$4,896,653.59</b>
<b>SAY TOTAL</b>						<b>\$4,900,000.00</b>